GLPS Early Learning Centre

PKF

10 August 2021 : GLPS Early Learning Centre

Summary Report

EM 'Latham Recessed Entry Mat'
VNL-1 'Gerflor Nerawood - 1451 Noma Kola'
VNL-2 'Gerflor Mipolam Elegance - 0343 Pecan' SKT-2 150mm COVED
VNL-3 'Gerflor Tarasafe Ultra - 8709 Granite' SKT-2 150mm COVED

Scale 1:430 (original drawing scale 1:100)

1 **Finishes Plan - Ground Floor**
Scale 1:100

FLOOR FINISHES LEGEND

VNL-1	Vinyl Flooring Type 1	
VNL-2	Non Slip Vinyl Flooring Type 2.	
VNL-3	Non Slip Vinyl Flooring Type 3.	
TIL-01	Exterior 300x600 Tile, as per schedule	
CONC-01	Concrete - Broom Fin.	
CONC-02	Concrete - Exposed Aggregate	
EM	Recessed Entry Matt	

NOTES:

1. Substitute plasterboard with villaboard in all wet areas
2. PB = Plasterboard
4. Refer Elevations for external cladding types & locations
5. Refer internal and external finishes schedules for further details.
6. Client to select wallpaper types.

RECESSED ENTRY MAT

Furnish and install Entry Mats to the following specification, as supplied by Latham Australia Pty Ltd.
ph +612 9879 7888, fax +612 9879 7666

Latham Roll-Up RDCC - recessed carpet entry mat (A)..... **900** ..... x (B)..... **1000** ..... in colour grey, aluminium to be standard clear anodised

Furnish and install Entry Mat Frames to the following specification, as supplied by Latham Australia Pty Ltd, ph +612 9879 7888, fax +612 9879 7666. Entry Mat Frame type AAF-aluminum standard size:112 x 12 x 3mm standard)(15 x 15 x 3mm)(20 x 20 x 3mm)(25 x 25 x 3mm)(30 x 30 x 3mm)(40 x 40 x 3mm)(50 x 50 x 3mm)/ACKD-10 aluminium cast-in place 45 x 90 x 12mm)/ (BCKD-10 brass cast-in place 25 x 25 x 3mm) to suit.

FEATURE WALL FINISHES LEGEND

WP-01	Feature Wallpaper 1
WP-02	Feature Wallpaper 2
WP-03	Feature Wallpaper 3

SKIRTING LOCATION LEGEND

SKT-1 = Timber Skirting Locations
SKT-2 = Wet Area Coving Locations

NOT FOR CONSTRUCTION

Finishes Plan - Ground Floor
scale:

elev tion ACHITECTURE
p 07 3251 6900
www.elevationarchitecture.com.au
info@elevationarchitecture.com.au

Rev	Description	Date
01	Tender Issue	2/07/2021
1	Tender Issue	2/07/2021
2	RFI 1_Tender Issue	26/07/2021

Rev	Description	Date

Figured dimensions take precedence over scale dimensions. Contractors must verify all dimensions on site before commencing any work or making shop drawings.

project
GLPS Early Learning Centre
18-38 & 16 Maine Road Clontarf QLD 4019 Australia
client
Grace Lutheran Primary School

Tender
architect: SC
drawn: MF
project no: **0501-14**
A-WD-08.01 **2**

Elevation Architecture Pty Ltd ACN 606 170 807 © Copyright reserved this document is and shall remain the property of Elevation Architecture. Unauthorised use of this document in any form whatsoever is prohibited.

BIMcloud: EA-SVR - BIMcloud Basic for ARCHICAD 23/3501-14_Master DD 23