

REQUEST FOR INFORMATION

PROJECT:	YOUTH SHELTER	REF NO:	1
TO:	Paul Curran	FROM:	Win Constructions Queensland
RE:	RFI [no.1] Joinery Information		

Please advise the following:

1. Benchtop finishes the schedule states laminated post formed tops; however, the plan view drawings have polar white compact laminate everywhere?
2. There are no dimensioned plans and finishes for the reception
3. The colour of the FAUX leather for the bench seats need a colour, density of the foam and the size of foam
4. Just confirming that the drop front vanity tops are to be compact as the laminate is white with the internal a solid black so you will see this on the front edge of these tops
5. The joinery inserts in the walls in the reception have no details and are only seen in the 3D perspective view

Thank you

Win Constructions Queensland



Win Constructions Queensland

ADDENDUM NO: 3

Project Number: 85285

Date: 16/05/2019

The following amendments set out here are to be incorporated in the tender documents and form part of the contract for **PIALBA - 42 Taylor Street, Design and Construction of 4x1 Bedroom Shared Living Plus Carers Room and Office.**

- The Joinery Details to the Reception Area can't be finalised at this stage. Include a PC allowance of \$12,500 as per attached **Returnable Schedule** for all the Joinery in the Reception Area which includes reception desk, wall inserts, bench seats, TV cupboard, bench seat covers and back rest.
- Benchtops are compact laminate.
- The drop front vanity tops are also compact laminate with mitred edges.

Please note that the tender closing date has been extended to Thursday 23 May 2019

You are required to include in your tender the work referred to in this addendum and to note this addendum number on your tender form.

Any enquiries should be directed to BASStrategicsourcing@hpw.qld.gov.au on **P: 07 3008 2371**