



QUOTE

ATG Project & Property Solutions Pty Ltd
Level 3 127 George St
BRISBANE CITY QLD 4000
AUSTRALIA
ABN: 94 160 517 493

Date
5 May 2021

Expiry
12 May 2021

Quote Number
QU-20579VAR#7

Reference
A125 VAR7

ABN
83 608 881 269

M7 Walls & Ceilings Pty
Ltd
19 Grenaside Court
QLD 4226

Mini Majors

Variation #7

Description	Quantity	Unit Price	GST	Amount AUD
This variation is necessary due to additional works.				
The period of any delay in the date for Practical Completion that will result from the variation is estimated at 7 business days.				
The change to the works is as follows:				
FIRE RATED BULKHEAD	1.00	1,403.64	10%	1,403.64
*Patch & repair existing 2HR fire rated bulkhead to rear of MM3				
*Remove existing Fyrchek plasterboard back to nearest joint, re sheet, set & fire mastic				
*300mm minimum stagger from previous layer				
*Issue form 16 for repairs only				
*Materials \$198.84				
*Labour \$1204.80				
FIRE RATED BULKHEAD	1.00	3,333.90	10%	3,333.90
*Install new horizontal 2HR fire rated bulkhead/ceiling into corridor.				
*Grid lines A & B, N3 & N4				
*Lost stud system due to ductwork				
*Issue form 16.				
*Materials \$924.30				
*Labour \$2,409.60				
SMOKE BULKHEAD	1.00	1,694.25	10%	1,694.25
*Supply & install new smoke bulkhead to rear of MM2				
*Materials \$ 0 (materials on site)				
*Labour \$1,694.25				

Description	Quantity	Unit Price	GST	Amount AUD
PARTITION	1.00	1,800.00	10%	1,800.00
*Supply & install new partition above D325 *Suitable steel stud with 2 layers of 16mm Fyrchek plasterboard to each side *FRL 120/120/120 *Issue form 16.				
FIRE RATING	1.00	492.40	10%	492.40
*Supply & install new Promat board fixed to the underside of concrete soffit to infill opening by new smoke riser *2HR fire rating *Issue form 16.				
FIRE RATED BULKHEAD	1.00	3,728.54	10%	3,728.54
*Patch & repair existing 2HR fire rated bulkhead to front of MM1 *Remove existing Fyrchek plasterboard back to nearest joint, re sheet, set & fire mastic *Supply & install shaft liner system *300mm minimum stagger from previous layer *Issue form 16 for repairs only *Materials \$678.89 *Labour \$3,049.65				
FIRE RATING	1.00	17,250.00	10%	17,250.00
*Supply & install suitable steel framing with 3 layers 16mm Fyrchek plasterboard to one side to wrap existing steel beams *Supply access equipment for M7 *Issue form 16.				
LEVEL 6	1.00	2,197.20	10%	2,197.20
*Supply & install Kingspan panels as per Bodans instruction *Materials \$691.20 *Labour \$1506.00				
			Subtotal	31,899.93
			TOTAL GST 10%	3,189.99
			TOTAL AUD	35,089.92

Terms

- All works based on standard work hours
- This quote is based on 14 days EOM payment terms
- This variation will change the price payable by the customer as per the above and will be taken into account on M7 Walls and Ceilings next scheduled progress claim if accepted.
- This quote is valid for 5 business days from date of quotation. Please respond within this time to ensure no unnecessary delays are incurred.
- I trust that this quotation suits your requirements, however, should you require any additional information please do not hesitate to contact me.

Kind Regards,

Lorna Merrick
M7 Walls and Ceilings