

Direct Cost Estimates

Pond Rectification - Kroll Gardens

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 3 Item No : 1.1 Site Establishment			Quantity : 1.000			LS	Contributing (Qty)		
1 Office and Compound									
2 =(2.5[#duration])	OFFICE.6X3	week	2.5000	60.000			150		150
3 =(2.5[#lq2])	CONTAINER.3X3	week	2.5000	31.000			78		78
4 =(2.5[#lq2])	TOILET.PORTABLE	week	2.5000	55.000			138		138
5	Float	each	4.0000	500.000			2000		2000
6	Sewer pump	each	4.0000	?????400.000			1600		1600
7 Water, signs, etc.	Misc Materials	Item	400.0000	1.000		400			400
8	FENCE TEMP MESH	M	150.0000	?????11.000		1650			1650
9	Labour	hr	5.0000	45.000	225				225
10									
11 Extra allowance for floats and deliveries									
12	Float	each	2.0000	500.000			1000		1000
13									
14 Access into pond									
15 =(2 No *5m wide * 0.6 high * 2.4m long * 0.5 *1.9[#Qfill])	Q - Select Fill	tonne	13.6800	15.200		208			208
16 =(13.68[#lq15])	Q - Tandem	tonne	13.6800	6.100		83			83
17	EXC 8	hr	4.0000	?????115.000			460		460
18	bob combo	hr	4.0000	90.000			360		360
19	Labour	hr	4.0000	45.000	180				180
20									
21 Remove Access									
22	EXC 8	hr	4.0000	?????115.000			460		460
23	bob combo	hr	6.0000	90.000			540		540
24	Labour	hr	4.0000	45.000	180				180
25 =(13.68[#lq15])	Tip - Clean Fill	tonne	13.6800	?????21.000				287	287
26									
27 Service Location									
28 Locate sewer	VAC EXCAVATION	HR	6.0000	?????170.000				1020	1020

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line	Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
29		VAC DISPOSAL	TONNE	2.0000	?????90.000				180	180
					11198.664	585	2341	6785	1487	11199

Line No :	4	Item No : 1.2	Environmental management verification and control	Quantity :	1.000	LS	Contributing (Qty)
1			CPSEC to draft plan and certify				
2			Engineer	hr	4.0000	?????180.000	720
3							
4			Inspection				
5			Engineer	hr	3.0000	?????180.000	540
					1260.000	1260	1260

Line No :	8	Item No : 2.1	Demolish and remove existing fence from site	Quantity :	1.000	LS	Contributing (Qty)
1			=(2lab * 8hr)				
			Labour	hr	16.0000	45.000	720
2			Small Tools/Equip	Item	1.0000	?????100.000	100
3			Skip	each	1.0000	?????450.000	450
					1270.000	720	550
							1270

Line No :	9	Item No : 2.2	Clear site of vegetation including debris, rubbish, small trees & shrubs	Quantity :	1.000	LS	Contributing (Qty)
1			Remove trees and fallen vegetation				
2			EXC 8	hr	6.0000	?????115.000	690
3			bob combo	hr	10.0000	90.000	900
4			=(34[#LR])	Tip - Green	34.0000	?????72.000	2448
5			=(1 trip*10*2)	Tip - Clean Fill	20.0000	?????21.000	420
6							
7			Slash long grass				

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line	Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
8		Labour	hr	5.0000	45.000	225				225
9		Small Tools/Equip	Item	1.0000	100.000			100		100
10										
11	Clean Fence									
12		Labour	hr	5.0000	45.000	225				225
13										
14	Strip Topsoil									
15	=(258.2[#LP]) Voume based on 200mm assumed depth			258.2000						
16		EXC 8	hr	10.0000	115.000			1150		1150
17		bob combo	hr	10.0000	90.000			900		900
18		Labour	hr	10.0000	45.000	450				450
19	Test topsoil	Gen Test	each	1.0000	350.000				350	350
					7858.000	900		3740	3218	7858

Line No :	10	Item No : 2.3	Bulk Earthworks - Cut & Fill	Quantity :	1.000	LS	Contributing (Qty)
1			Calculations				
2			=(106) cut volume		106.0000		
3							
4			Earthworks will take 2 days due to tracking between ponds and needing to construct sandstone wall for portion				
5			Therefore, assume two 7.5 hour days, not 10hr				
6							
7			Cut to Fill				
8			=(2 * 7.5)				
9			=(15[#lq8])				
10			Roller 2t	day	2.0000	200.000	400
11			=(15[#lq8])				
12							
13			Trim subgrade for gravel section				
14							
			EXC 8	hr	2.0000	115.000	230
					4380.000	675	3705
							4380

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
--------------	----------	------	----------	------	--------	----------	-------	----------	-------

Line No :	11	Item No : 2.4	Fill with Imported Soil (including additional 30%)	Quantity :	1.000	LS	Contributing (Qty)			
1 Calculations										
2	=(140) Fill				140.0000					
3	=(106*0.85) compacted cut				90.1000					
4	=(17*0.85) compacted spoil)				14.4500					
5	=((140[#lq2]-90.1[#lq3]-14.45[#lq4])*1.3) import				46.0850					
6										
7 Build Up										
8	Material									
9	=(46.085[#lq5]*2.2)			Q - Select Fill	tonne	101.3870	15.200	1541	1541	
10										
11	Placement									
12				bob combo	hr	4.0000	90.000	360	360	
13				Roller 2t	day	1.0000	200.000	200	200	
14				Labour	hr	4.0000	45.000	180	180	
						2281.082	180	1541	560	2281

Line No : 12	Item No : 2.5	Fill with Road base	Quantity :	1.000	LS	Contributing (Qty)	
1 Qty from plans							
2	=(160) area			160.0000			
3	=(19) volume			19.0000			
4							
5 Build Up							
6 Materials							
7	=(19[#lq3]*2.4[#Qgravel]*1.07[#waste])		CBR 15	tonne	48.7920	17.200	839 839
8	=(48.792[#lq7])		Q - Tandem	tonne	48.7920	6.100	298 298
9							
10 Placement							

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
11	EXC 8	hr	4.0000	115.000			460		460
12	bob combo	hr	6.0000	90.000			540		540
13 Use trench roller or large plate/hand held roller	Roller 2t	day	1.0000	200.000			200		200
14 Deliver roller	Float	each	0.5000	500.000			250		250
15 =(6[#lq12]*2 lab)	Labour	hr	12.0000	45.000	540				540
16									
17 Trim									
18	EXC 8	hr	2.0000	115.000			230		230
19									
20 =st(6:18,19[#lq3]) \$ per cube				176.677	540	1137	1680		3357
				3356.854	540	1137	1680		3357

Line No : 13	Item No : 2.6	Trimming to levels	Quantity : 1.000	LS	Contributing (Qty)
1 Base Qty					
2 =(1291 earthworks area			1291.0000		
3 =(65) length of swale			65.0000		
4 =(1800) production m2 per day			1800.0000		
5					
6 Build Up					
7 =roundup((1291[#lq2]/1800[#lq4])*10)	EXC 8	hr	8.0000	115.000	920
8 =(8[#lq7])	bob combo	hr	8.0000	90.000	720
9	Bobcat attachment	day	1.0000	25.000	25
10 =(8[#lq7])	Labour	hr	8.0000	45.000	360
11 =st(7:10,1291[#lq2])			1.569	360	1665
12					
13 Swale trim	EXC 8	hr	2.0000	115.000	230
14					
15 =st(13,65[#lq3]) \$ per m				3.538	230
				2255.000	360
					1895
					2255

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 14 Item No : 2.7 Loading, transporting & disposal of excess unsuitable spoil from site including tip fees (provisional quantity) Quantity : 130.000 m3 Contributing (Qty)									
1 =(1291*(0.2-0.1)) excess topsoil due to assuming 200mm strip but only 100mm respread			129.1000						
2 =(129.1[#lq1]*1.7) bulked volume			219.4700						
3 =(219.47[#lq2]/20) truck and dog loads			10.9735						
4									
5 Transfer station is under 1km away									
6 Half a day operation with 2 trucks									
7									
--8	EXC 8	hr	5.0000	115.000				-575	-575
--9 =(5[#lq8]*2-trucks)	Truck and Dog	hr	10.0000	115.000				-1150	-1150
--10 =(5[#lq8])	Labour	hr	5.0000	45.000	225				225
--11 =(129.1[#lq1]*1.9[#Qfill])	Tip - Clean Fill	tonne	245.2900	21.000				-5151	-5151
12									
13									
14 Remove topsoil via haulage									
15	EXC 8	hr	10.0000	115.000			1150		1150
16 =(219.47[#lq2])	Export - Topsoil	m³	219.4700	15.000				3292	3292
17	Labour	hr	10.0000	45.000	450				450
18									
19 Removal of general waste materials									
20	bob combo	hr	10.0000	90.000			900		900
21	Tip - Clean Fill	tonne	20.0000	21.000				420	420
				47.785	450		2050	3712	6212

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 18 Item No : 3.1	Pedestrian Safety Fence - 1.3m high (Refer Std. Drg. SF-1510)		Quantity : 25.200						
1 Quote from Ford Brothers									
2 =(25.2[#QTY])	1.2m fence	m	25.2000	150.000				3780	3780
				150.000				3780	3780
Line No : 19 Item No : 3.2	Preparation of surface other than stepped batters		Quantity : 1.000						
1	L Prep	m²	1575.0000	??0.580				914	914
				913.500				914	914
Line No : 20 Item No : 3.3	Spread topsoil from stockpile		Quantity : 1.000						
1 Calculations									
2 =(130) respread volume			130.0000						
3 =(180) production per day			180.0000						
4									
5 Build Up									
6 =(130[#lq2]/180[#lq3])*10)	EXC 8	hr	7.2222	115.000				831	831
7 =(7.2222[#lq6])	bob combo	hr	7.2222	90.000				650	650
8 =(7.2222[#lq6])	Tandem	hr	7.2222	85.000				614	614
9 =(7.2222[#lq6])	Labour	hr	7.2222	45.000	325				325
10									
11 =st(6:10,130[#lq2])				18.611	325			2094	2419
				2419.437	325			2094	2419

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 21 Item No : 3.4	Cultivation - Ripping and amelioration of subsoil - 150 deep		Quantity : 1,575.000			m2		Contributing (Qty)	
1 =(1575[#QTY])	L Cultivation	m²	1575.0000	???????5.490				8647	8647
				5.490				8647	8647
Line No : 24 Item No : 3.5	Supply and Install Sir Walter (Shade) or Sea Isle (Coastal) Turf as specified		Quantity : 100.000			m2		Contributing (Qty)	
1 =(100[#QTY])	Turf	m²	100.0000	???????3.500		350			350
2 Pick up turf - small qty	Tandem	hr	1.0000	85.000			85		85
3 =(2 labs *3hr)	Labour	hr	6.0000	45.000	270				270
				7.050	270	350	85		705
Line No : 27 Item No : 3.6	Tube stock		Quantity : 3,915.000			each		Contributing (Qty)	
1 =(3915[#QTY])	Tubestock	each	3915.0000	???????2.500				9788	9788
				2.500				9788	9788
Line No : 28 Item No : 3.7	140mm pot		Quantity : 160.000			each		Contributing (Qty)	
1 =(160[#QTY])	140 pot	each	160.0000	???????6.200				992	992
				6.200				992	992

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 29 Item No : 3.8	Plant and Landscape Maintenance		Quantity : 1.000			LS		Contributing (Qty)	
1 Watering									
2 =(6weeks*5visits) first phase			30.0000						
3 =(5weeks*3visits) second phase			15.0000						
4 =(4weeks*2visits) third phase			8.0000						
5 =(30[#lq2]+15[#lq3]+8[#lq4])*2hrs)	Watercart	hr	106.0000	95.000			10070		10070
6									
7 Maintenance									
8	L Establish	week	12.0000	?????350.000				4200	4200
				14270.000			10070	4200	14270
Line No : 30 Item No : 3.9	Supply and place Hoop Pine Mulch		Quantity : 1,230.000			m2		Contributing (Qty)	
1 =(1230[#QTY]*0.075)	L - Mulch	m³	92.2500	?????28.000				2583	2583
2 =(2lab * 10hr)	L - Labour	hr	20.0000	?????35.000				700	700
3	Small Tools/Equip	Item	1.0000	?????100.000			100		100
				2.750			100	3283	3383
Line No : 34 Item No : 4.1	Supply and install 400x400x1000mm Sandstone Block Wall as detailed and specified		Quantity : 45.000			unit		Contributing (Qty)	
1 Materials									
2 =(45[#QTY]*1.07[#waste])	Boulder A	m	48.1500	86.400		4160			4160
3									
4 Placement									
5	EXC 8	hr	10.0000	?????115.000			1150		1150
6	Labour	hr	5.0000	45.000	225				225
7									
8 Grout Gaps									
9	Labour	hr	5.0000	45.000	225				225

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line	Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
10		Conc Min	Item	1.0000	??????300.000		300			300
					134.670	450	4460	1150		6060

Line No :	38	Item No : 5.1	Traffic/Pedestrian Management	Quantity :	1.000	LS	Contributing (Qty)
1			Access to site from gates along Duffield St - no TC required				
2			=((300[#lq2]*2)/4crs)	300.0000			
3							
4			Create flagged access track				
5			=((300[#lq2]*2)/4crs)	150.0000	7.500		1125
6			=roundup(150[#lq5]/100)	2.0000	41.000		82
7			=((300[#lq2]*2*2rows)/100)	12.0000	44.000		528
8			=((2labs *10hrs)	20.0000	45.000	900	900
9							
10			=st(5:8,300[#lq2]*2)		4.392	900	1735
11							
12			Allowance for signs	500.0000	1.000		500
13							
14			Additional labour time to open and close gate for delivers and general communication with park users				
15			=((2.5[#duration]*5days*2hr) Extra hour a day	25.0000	45.000	1125	1125
16							
17							
18			=((20[#lq8]) remove flagging	20.0000	45.000	900	900
					5160.000	2925	2235
							5160

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 42 Item No : 6.1	Erosion and sedimentation control		Quantity : 1.000						
					LS	Contributing (Qty)			
1	Silt Fence	m	100.0000	???????4.500				450	450
2	Min Charge	each	1.0000	?????200.000				200	200
3 =(2.5[#duration]*5days)	Water trailer	day	12.5000	?????200.000			2500		2500
4 =(12.5[#lq3]*2000l per day)	Water Supply	litre	25000.0000	???????0.010		250			250
5 =(2.5[#duration]*2 days*2hr)	STREET SWEEPER	HR	10.0000	?????110.000			1100		1100
6	Misc Materials	Item	500.0000	1.000		500			500
				5000.000		750	3600	650	5000

Line No : 46	Item No : 7.1	Excavate, bed, lay, joint and backfill with imported material by depth. - 300mm SRCP (Depth less than 1.5m)	Quantity :	26.600	m	Contributing (Qty)	
1 Calculations							
2	=(26.6[#QTY])			26.6000			
3	=((7.6-6.8)+0.15) Depth			0.9500			
4	=(0.4+0.15+0.15) Width			0.7000			
5	=(cirarea(0.2)) Pipe area			0.1257			
6	=(0.95[#lq3]*0.7[#lq4]*26.6[#lq2]) Spoil volume			17.6890			
7	=(17.689[#lq6]-(26.6[#lq2]*0.1257[#lq5])) Bedding volume			14.3454			
8							
9 Build Up							
10 Materials							
11	=(14.3454[#lq7]*2.2[#Qagg]*1.07[#waste])	Drainage 20mm	tonne	33.7691	27.200	919	919
12							
13 Excavation							
14	=(26.6[#QTY]*1.33) production m per day			35.3780			
15	=(26.6[#QTY]/35.378[#lq14]*10)	EXC 8	hr	7.5188	?????115.000	865	865
16	=(7.5188[#lq15])	Backhoe	hr	7.5188	?????115.000	865	865
17	=(7.5188[#lq15])	Pipe Fore	hr	7.5188	?????85.000	639	639
18	=(7.5188[#lq15]*2 labs)	Pipe Lab	hr	15.0376	?????65.000	977	977
19		Small Tools/Equip	Item	1.0000	?????100.000	100	100

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
20									
21 Note - Spoill to be placed in fill location									
				164.075	1617	919	1829		4364
Line No : 47	Item No : 7.2	Supply and deliver of drainage pipes. - 300mm SRCP Class 2 RRJ	Quantity : 26.600						
1 =(26.6[#QTY]/2.44) lengths			10.9016						
2 =roundup(10.9016[#lq1]*2.44)	P-300-3	m	27.0000	45.150		1219			1219
3	Delivery	Item	1.0000	??????250.000		250			250
				55.227		1469			1469
Line No : 48	Item No : 7.3	Supply and install 300mm Precast Headwall	Quantity : 2.000						
1 =(2[#QTY])	H-300	each	2.0000	268.770		538			538
2 =(2[#QTY]*1hr)	Backhoe	hr	2.0000	??????115.000			230		230
3 =(2[#lq2]*2)	Pipe Lab	hr	4.0000	??????65.000	260				260
4	Misc Materials	Item	100.0000	1.000		100			100
				563.770	260	638	230		1128
Line No : 49	Item No : 7.4	Supply and Place Rock Spalls (to 150 nom. Dia.)	Quantity : 2.400						
1 Material									
2 =roundup(2.4[#QTY]*0.25*2.2[#Qagg])	Rock 150-250	tonne	2.0000	33.200		66			66
3 =(2[#lq2])	Q - Tandem	tonne	2.0000	6.100		12			12
4 =roundup(2.4[#QTY]*2)	Geofab A24	m²	5.0000	????????1.500		8			8
5 Assume order full tandem to use in other works									
6									
7 Placement									

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
8	bob combo	hr	2.0000	90.000			180		180
9	Labour	hr	2.0000	45.000	90				90
				148.375	90	86	180		356

Line No : 50	Item No : 7.5	Field Inlet Pit - Type 2A (600 x 600)	Quantity :	1.000		each	Contributing (Qty)		
1	Materials								
2	=(1[#QTY])	600x600 pit	each	1.0000	258.080		258		258
3	=(1[#QTY])	600x600 grate D	each	1.0000	262.600		263		263
4	=(.6*4*0.2*2.2[#Qagg])	Drainage 20mm	tonne	1.0560	27.200		29		29
5									
6	Installation								
7		EXC 8	hr	2.0000	?????115.000			230	230
8		Backhoe	hr	2.0000	?????115.000			230	230
9		Pipe Fore	hr	2.0000	?????85.000	170			170
10	=(2[#lq9]*2)	Pipe Lab	hr	4.0000	?????65.000	260			260
					1439.403	430	549	460	1439

Line No :	51	Item No : 7.6	Break into existing pit/manhole	Quantity :	3.000	each	Contributing (Qty)				
1			SAW TRAVEL	each	1.0000	90.000			90	90	
2		=(3[#QTY]*(200/10))	SAW.CORE.WALL.300	each	60.0000	?????15.000			900	900	
3			SAW WATER	each	1.0000	100.000			100	100	
4											
5		Render Hole and pipe									
6		=(3[#QTY]*1hr)	Pipe Lab	hr	3.0000	?????65.000	195			195	
7			Conc Min	Item	1.0000	?????300.000		300		300	
8			Small Tools/Equip	Item	1.0000	?????100.000		100		100	
						561.667	195	300	100	1090	1685

Direct Cost Estimates

Printed : January 13, 2020 12:04:22

Line Comment	Resource	Unit	Quantity	Rate	Labour	Material	Plant	Subcont.	Total
Line No : 52 Item No : 7.7	Flood/Tide Gate or Valve to Outlet - 300 pvc		Quantity : 1.000			each		Contributing (Qty)	
<u>1</u> <u>Materials</u>									
2	300mm Flap End	each	1.0000	?????250.000		250			250
3 Buy 3m length	PVC 300	m	3.0000	?????75.000		225			225
4 Glue	Misc Materials	Item	50.0000	1.000		50			50
5									
<u>6</u> <u>Placement</u>									
7	Pipe Lab	hr	2.0000	?????65.000	130				130
				655.000	130	525			655
Line No : 53 Item No : 7.8	Supply, place and certify water-tight liner to frog pond		Quantity : 160.000			m2		Contributing (Qty)	
1	Mobilisation	m ²	1.0000	????5000.000				5000	5000
2 =(160[#QTY])	1.5mm HDPE	m ²	160.0000	?????20.000				3200	3200
3 Stainless steel fittings	Misc Materials	Item	250.0000	1.000		250			250
				52.813		250		8200	8450