

MATERIAL COSTS

Items	Quantity	Hours	Days	Weeks	Cost	Total material cost
Lintels (steel angles 1200x100x100mm) - 50m needed	42			1	\$33.00	\$1,386.00
Prop hire (approx 1 every 1m)	64			2	\$18.00	\$2,304.00
Mixer (65L)	1			1	\$499.00	\$499.00
Shovels	2			1	\$11.60	\$23.20
Skip bin hire (upto 14 days)	1			1	\$300.00	\$300.00
Cutting water saw hire	1			2	\$510.00	\$1,020.00
Scaffold hire (upto 14 days) (x5 trestles, 4 6m planks, 5 plank clamps)	1			1	\$672.00	\$672.00
Mixing compound 20kg bag (26 clay bricks per bag)	223.4			1	\$10.50	\$2,345.70
Brick (120x280mm)	5808			1	\$1.80	\$10,454.40
Stringline (100m)	3			1	\$6.00	\$18.00
Freight costs						
Skip bin delivery	1			1	\$99.00	\$99.00
Prop delivery	1			1	\$40.00	\$40.00
Scaffold delivery	1			1	\$110.00	\$110.00
Labour						
Bricklayers	2	8	10	2	\$42.00	\$6,720.00
Labourer	1	8	10	2	\$35.00	\$2,800.00
					Total excl GST:	\$28,791.30
					GST calculated:	\$2,879.13
					TOTAL inc GST:	\$31,670.43

Notes:

Mortar compound lays 26 bricks per bag

Scaffod above 3m to be supplied by builder

Lintels supplied for openings greater then 600mm

197.47m2 for brick area

Wastage: 188m2 x 5% = 9.4

m2 per brick: 120mm x 280mm= 0.03

Total bricks need: 197.47m2 / 0.034= 5808

Labour: Bracklayer - \$42/hr, Labourer - \$35/hr

As per the QBCC Technical qualifcations for licensing document:

All labour contracted must hold a Cert 3 in Bricklaying/Blocklaying or a recognition certificate as a qualified brick/block layer.